






Purpose




This presentation intends to showcase:

The effectiveness and reliability of MCA's Chain Jack engineering solution to COB installation


The efficiency and reliability of MCA Engineering to install and implement this solution





CADIA EXPANSION PROJECT- COB Can and Rail Mat Installation





MCA was Engaged by Newcrest to install COB Can and Rail Mats into an excavated shaft between an *Ore Crushing Station* and a *Collection Conveyor* as part of the Scope of Facilities in the Cadia Expansion Project.

This excavation was approximately 32 m deep and 6.6 m in diameter.

Installed into this excavation was approximately 85 tonnes of COB Cans and 162 tonnes of Rail Mat Liners

Project Summary



Project Requirements


Specialised and Engineered Installation Equipment:

- Operation and Maintenance Manuals
- Design Calculations, Documents and Drawings
- Factory Acceptance Testing of Lifting/Lowering Mechanism

Underground Works:


- Labor, Supervision and Equipment for all construction and installation
- Install chairing structure, hydraulic power pack, jacking system and chain drums
- Assemble and install Can sections
- Scribe underside of bin brow for Shotcrete plug
- Oversee concrete placement to backfill annulus
- Clean up and demobilisation from site

Project Outcomes



Design and Fabrication






Installation Process – 1. Walkway Ring





Transported Blow Surface



Lifted via Franna Crane onto position over shaft

Anchored into position around shaft




Installation Process – 2. Jacking Beams




Changed out Walkway Spaces for Drill Templates





Drilled and Installed Bolts 3.5 m deep

Installed Jacks and Jack beams onto position over shaft






Grouted Jack Beam Plates



Pull tested anchor bolts to 22 tonnes for 15 minutes

Installation Process - 3. Finalised Hydraulic System Installation



Installation Process - 4. Transported, Assembled & Installed Cans





Transported Cans Below Surface




Assembled below ground



Lifted into position in shaft



Bolted onto top flange of previous Cans



Bottom Can Collection Level



Repeated until all 12 Cans were installed

Installation Process - 5. Backfill Anulus





Installed scribing mesh







Created plug with 90 cubic meters of shotcrete

Backfilled anulus



Installation Process - 6. Rail Mats



- Transported Rail Mats to
 Collection Level
- Set them up onto cradles





- Attached 5 Rail Mats onto lifting gig
- Hoisted up gig with Crane at the top of the shaft
- Attached Mats to inside diameter of Cans by J bolts and welding nuts

Repeated until all 300 Rail Mats were installed

 \mathbf{C}





Timeline



Rail Mats										
Backfill										
Cans Hydraulic System										
Jacking Beams										
Walk Way Ring										
Mobilisation										
DATE:	9/01/2022	10/01/2022	11/01/2022	12/01/2022	13/01/2022	14/01/2022	15/01/2022	16/01/2022	17/01/2022	18/01/2022
Rail Mats										
Backfill Cans										
Hydraulic System										
Jacking Beams										
Walk Way Ring										
Mobilisation										
	19/01/2022	20/01/2022	21/01/2022	22/01/2022	23/01/2022	24/01/2022	25/01/2022	26/01/2022	27/01/2022	28/01/2022
Rail Mats Backfill										
Cans										
Hydraulic System										
Jacking Beams										
Walk Way Ring										
Mobilisation DATE:	29/01/2022	20/01/2022	31/01/2022	1/02/2022	2/02/2022	3/02/2022	4/02/2022	5/02/2022	6/02/2022	7/02/2022
Rail Mats	25/01/2022	30/01/2022	51/01/2022	1/02/2022	2/02/2022	3/02/2022	4/02/2022	3/02/2022	0/02/2022	7/02/2022
Backfill										
Cans										
Hydraulic System										
Jacking Beams										
Walk Way Ring Mobilisation										
DATE:	8/02/2022	9/02/2022	10/02/2022	11/02/2022	12/02/2022	13/02/2022				

Contact Us



Ph: 1300 528 535

info@mcagroup.com.au

www.mcaengineering.com.au



Head Office

111 Glenwood Drive PO Box 3202 Thornton, NSW 2322